

Centrifuge Operation SOP

LAB SOP | Version 1.3 | Effective 2026-07-15 | DEMO DOCUMENT

1. Pre-run check

- Inspect rotor, buckets, and tube condition.
- Confirm tube pairs are balanced by mass and position.

2. Run

- Secure the rotor lid and close the chamber.
- Set RCF, duration, and temperature according to the protocol.

3. After use

- Wait for a complete stop before opening.
- Wipe spills, leave the chamber dry, and record the run.